



भाकअनुप - केन्द्रीय बारानी कृषि अनुसन्धान संस्थान

ICAR - Central Research Institute for Dryland Agriculture

संतोषनगर, सैदाबाद-पोस्ट हैदराबाद ५०००५९ Santoshnagar, Saidabad P.O. Hyderabad 500 059
040-24530161,24530163,2Fax:040-24531802 www.icar-crida.res.in Email : hoa.crida@icar.gov.in



e-F.No: 4-7/(73)/2023-24/CDN
Date:10.05.2024

Sub: Quotations for Repairs, External & Internal Painting of CRIDA Research Farm Phase -III Farm Office Building (Indana), at HRF - Hayathnagar – reg.

Dear Sir(s),

Quotations are invited for following Repair/Works as detailed below:

SL NO	NAME OF THE WORK	PARTICULAR
1	Repairs, External & Internal Painting of CRIDA Research Farm Phase - III Farm Office Building (Indana), at HRF - Hayathnagar	as per enclosed specifications

TERMS & CONDITIONS

- The last date for submission of quotation is **03.06.2024**. Rates offered shall be F.O.R. CRIDA, Hyderabad
- The work shall be carried out as per this Institute Specification and as per the directions of Institute Chairman, IWMC or and Indenting officer and the payment will be made after satisfactory completion of work duly certified by the Indenting Officer
- Quotations should be submitted in a sealed cover addressed to the Director, Central Research Institute for Dryland Agriculture, Santoshnagar, Saidabad Post, Hyderabad – 500 059. The cover containing quotation should invariably be super scribed.
 - Due on 03.06.2024 16.00 hrs**
 - For supply of material for repairs / masonry / Digging / plastering works etc.
- The quotation should remain valid for a period of 90 days from the date (due date)
- No advance payment/delivery against payment is permissible. However, the payment shall be arranged in 15 days from the date of submission of pre-receipted bill in triplicate along with stores.
- The rates quoted should be net payable for each item/material for delivery at the Institute at the address given above (inclusive of all taxes-GST, packing, forwarding, transport, insurance and excluding rebate/discount etc.)
- While quoting the rates please mention the following:
 - Approximate time for supply of material from the date of placing order.
 - Guarantee/Warranty/Expiry period
 - Any other condition
- The participating bidder must submit a copy of GST and PAN card
- Time allowed for completion of the work 30 days
- Quotation which do not conform to the above terms and conditions will not be considered. The Director, Central Research Institute for Dryland Agriculture, reserves the right to accept or reject any or all quotations without assigning any reasons thereof.

(V. Sanu)
Administrative Officer

TECHNICAL SPECIFICATIONS/SCOPE OF WORK**Repairs, External & Internal Painting of CRIDA Research Farm Phase -III Farm Office Building (Indana), at HRF - Hayathnagar**

Sl.no	DSR item No	Description	Nos	QTY	Unit Rate	Unit	Amount	Remarks
1	DSR no:14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	1	10		sqm		
2	DSR no:14.10	Refixing old glass panes with putty and nails	1	5		sqm		
3	DSR no:13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc.	1	145.54		sqm		
4	DSR no:13.87.1	White washing with lime to give an even shade : Old work (two or more coats) .	1	225		sqm		
5	DSR no:13.111.1	Finishing walls with Acrylic Smooth exterior paint of required shade :Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface.	1	55		sqm		
6	DSR no:13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	1	20		sqm		
7	DSR no:2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	1	15		cum		
8	DSR no:4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) cum 7783.65	1	7		cum		
9	MR	Sintex 1000L 1240mm 4 Layer White Water Tank, CCWS-0100-01-DW-WHITE ₹10,204	1	1		nos		
10	MR	Deep cleaning of toilets	1			LS		
	MR	Pvc Sewer Pipe for Plumbing work	1	20		Rm		
11	MR	Electrical miscellaneous items and santairy items	1			LS		
		Total Amount						
		GST						
		Contingency if any						
		Grand Total						

Handwritten signature and date: 15/05/24